



MOOSEHEAD CEDAR LOG HOMES

Standard Package:

The Poacher (880 sq.ft)	\$22,795
The Little Wilson Pond (864 sq.ft.) .	\$24,495
The Six Rivers (700sq.ft.)	\$23,650
The Winterhaven (633 sq.ft.)	\$18,945
The Hunter (320 sq.ft.)	\$11,695

With Optional Interior Package:

The Poacher (880 sq.ft)	\$24,695
The Little Wilson Pond (864 sq.ft.) ..	\$30,845
The Six Rivers (700sq.ft.)	\$24,940
The Winterhaven (633 sq.ft.)	\$21,345
The Hunter (320 sq.ft.)	\$13,345

Prices are effective through
May 1, 2004 for delivery in 2004.

These homes are based on weathertite versions
of models and are available with optional interior door
and partition packages.

Options vary, please consult our design office for
specific details.

Moosehead Cedar Log Homes
Regional Sales Center & Model Home
www.mooseheadloghomes.com

Area Representative: Robert Smith
PO Box 72, 586 Cedar Lane, Greenville, NY 12083
Phone: 518-966-4289 • Fax: 518-966-5930
E-mail: moosehdny@aol.com

Model Available by Appointment

Standard Package:

1. Sills: Pressure Treated 2" x 6" - 2" x 4".
2. Girders: (3) 2" x 10" or (4) 2"x10" Spruce.
3. Headers and Rim Joists: Spruce.
4. Floor Joists and Blocking: 2" x 10" Spruce.
5. Subfloor: 5/8" Sheathing.
6. Milled 6" x 6" Camp Grade Cedar.
7. Milled T&G Log Siding for Floor Frame Skirting.
8. 4" x 8" Beam Ceiling Joists.
9. Beam Trusses: 6" x 6", 6" x 8", or 6" x 10", pre-cut to length & angle.
10. Roof Purlins: 6" x 6" Precut.
11. Roof Decking: 1st Roof Deck – 3/4" T&G
2nd Roof Deck – 5/8" Sheathing
12. Roof Strapping: 1"x 4" Double Strapping.
13. Felt Paper: 15# Asphalt Rolls.
14. Galvanized Drip Edge.
15. Shingles: 25-year.
16. Pre-Hung 9 Lite, Brosco Exterior Doors w/locksets.
17. Tilt Double-Hung Windows w/Screens.
18. 6" x 6" Wall Braces Where Required.
19. Fascia: 1" x 8" Pine.
20. Porch Floor Framing: 2" x 8" Pressure Treated.
21. Porch Floor: 5/4 Spruce Decking.
22. Deck Floor: 5/4 Cedar Decking.
23. Porch Railing: 2" x 4" Cedar.
24. Porch Rafters: 4" x 6" Spruce.
25. Porch Roof Deck: T&G Spruce w/
5/8" Sheathing for Second Roof Deck.
26. Porch Post: 6"x 6" Spruce.

Optional Interior Package:

1. Framing: 2" x 4" and 2" x 6" Shoe, Double Plate, Studs, Blocking, Headers and Fillers as Necessary.
2. V-Groove Boards for Interior Partitions on both sides.
3. Loft Flooring: 5/4" T&G Decking.
4. 6 Panel, Solid Pine Interior Doors w/Locksets
5. Loft Stairs: 2" x 12" Stringers with 2" x 12" Treads, 1" x 8" Risers, and 2" x 4" Handrail.
6. Loft Railing: 2" x 4" Cedar.
7. All Interior Trim: 1" x 4" Spruce.

Note: Rigid insulation by others.